



By appointment to
Her Majesty The Queen
Building Façade Restoration
and Conservation



1 – 5 New Bond Street

The replacement of three domes in the centre of London's most prestigious shopping street proved a challenge. The original Portland Stone domes were leaking due to steel corrosion and were removed. PAYE were employed to design, supply and install three new domes to replicate the originals. Planning regulations stipulated their construction must be solid and not made of G.R.P.

The domes were made in eight segments with a central keystone and weighed 21 tonnes each. In order to get the domes in place, they had to be craned up five floors and this meant doing the job at weekends.

The segments were set 15mm above their final position and when all eight were in place, they were all lowered and the keystone inserted to lock the segments in place.

- **Cleaning**
- **Repair**
- **Conservation**
- **Extension**
- **Adaption**
- **Surveys**
- **Budgets**
- **Technical advice**



PAYE

www.payestone.co.uk

Stationmasters House **Mottingham Station Approach** London **SE9 4EL**
Telephone 020 8857 9111 Fax 020 8857 9222
enquiries@payestone.co.uk